DLB SUPER CHIEF

MORRISON
DELIVERING ENERGY



KEY FEATURES

- Climate controlled surface dive chambers on vessel
- Capable of utilizing automatic welding systems
- Capable of handling pipe up to 36 in diameter
- Stable vessel due to molded bow design
- Project specific stinger design available

Dimensions

- **LENGTH (WITH APRON):** 265 ft
- **WIDTH:** 72 ft
- **DEPTH:** 16 ft
- **ACCOMMODATIONS:** 91 personnel

Classifications

- **US FLAG**
- **USCG COI**
- **ABS CLASSED:** #9938791

Rev20263

HOUSTON, TEXAS

16285 Park Ten Place, Suite 120
Houston, TX 77084
713.344.9233

CORPORATE MAILING ADDRESS

PO Box 3301
Houma, LA 70361

US | Mexico | West Indies

MorrisonEnergy.com

Capacities

- **FUEL:** 138,150 gal
- **WATER:** 153,500 gal
- **BALLAST:** 300,020 gal

Generators

- **1000 KW**
- **1000 KW**
- **150 KW -** Emergency generator

Air Compressors

- **DECK UNIT:** 375 cfm

Welding Machines

- **(8) MILLER:** 400 amp DC

Cranes

- **MANITOWOC:** 4000 boom length 130 ft
- **NAUTILUS MAIN:** 7 st @60 ft
- **NAUTILUS AUX:** 2.9 st @70 ft

Mooring

WINCHES

Amcon 625 series 2-drum (bow)

- **WIRE ROPE:** 6,000 ft x 1.5 in
- **STALL RATING:** 112.5 st
- **BRAKE HOLDING POWER:** 122.5 st
- **LINE SPEED:** Max - 658 FPM / 200 mpm full drum

Amcon 750 series 2-drum (bow)

- **WIRE ROPE:** 6,000 ft x 1.5 in
- **STALL RATING:** 169 st
- **BRAKE HOLDING POWER:** 300 st
- **LINE SPEED:** Max - 539 FPM / 165 mpm full drum

(2) Skagit 97 series 2-drum (stern)

- **WIRE ROPE:** 4,000 ft x 1.5 in x 38 mm per drum
- **STALL RATING:** 112.5 st
- **BRAKE HOLDING POWER:** 100 st
- **LINE SPEED:**
  Max - 248 FPM / 75.6 mpm full drum
  Min - 30 FPM / 9.14 mpm bare drum

ANCHORS

- **DELTA FLIPPER STANDARD:** (8) 7.5 st
- **BRUCE TWIN SHANK AVAILABLE:** Up to 14 st

Pipelay equipment

- **FIRING LINE:**
  Covered and weatherized
- **(5) WORK STATIONS:**
  (3) Welding
  (1) X-Ray
  (1) Field joint stall
- **PIPE TENSIONER:**
  100 kips (PDI track type)
  50 kips (PDI track type)
- **PDI HANDLING EQUIPMENT:**
  3 in to 36 in including coating
- **A&R WINCH:**
  100 kips (Intercon) hydraulic
- **STINGER (FIXED):**
  75 ft length
  (Project specific stinger design available)

Pipe burial equipment

- **BURIAL SLEDS:**
  Conventional pull style (standard)
- **DECK JET PUMPS:**
  10 in x 10 in

SPECIFICATIONS ARE SUBJECT TO CHANGE WITHOUT NOTICE